

## FOUNDATION NOTES:

- 1. CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS: 3000 PSI --- NORMAL WEIGHT --- UNLESS NOTED
- 2. REINFORCING BARS: ASTM A615 GRADE 60.

WATER / CEMENT RATIO 0.45 OR LESS


- 3. WELDED WIRE FABRIC (WWF): ASTM A185. 6  $\times$  6 W2.9/2.9
- 4. REINFORCING BAR PLACING ACCESSORIES IN ACCORDANCE WITH ACI MANUAL OF STANDARD PRACTICE.
- 5. DETAIL REINFORCEMENT IN ACCORDANCE WITH ACI 315. REINFORCEMENT SHALL NOT BE WELDED UNLESS NOTED OR APPROVED BY THE ENGINEER.
- 6. LAP ALL REINFORCEMENT SPLICES A MINIMUM OF 30 BAR DIAMETERS BUT NOT LESS THAN 1'-0", UNLES NOTED.
- 7. CONCRETE COVERAGE OF REINFORCEMENT: GRADE BEAMS --- 3" BOTTOM AND SIDES, 2" TOP.
- 8. EARTH SUPPORTED SLABS: (INCLUDING EXTERIOR WALK AND DRIVE SLABS) 4" THICK. REINFORCED WITH 6 x 6 W2.9/2.9 WWF AT MID-DEPTH OF SLAB, UNLESS NOTED.
- 9. CONCRETING OPERATIONS SHALL COMPLY WITH ACI STANDARDS.
- 10. ALL UNDERSLAB AREAS TO BE TREATED FOR TERMITES BY A LICENCED APPLICATOR. OWNER TO RECEIVE RENEWABLE BOND.
- 11. ALL FOOTINGS TO BEAR ON UNDISTURBED SOIL OR COMPACTED FILL OF 95% DENSITY.














HANDRAIL DETAIL SCALE: 3/4" = 1'-0"

HEATED AND COOLED TOTAL AREA: 1100 S.F.

FRONT PORCH: 180 S.F.

545 East 21<sup>st</sup> Avenue \_

## #3 SPE

JOB NO.: 203 DATE: 03/27/02 SCALE: 1/4"=1'-0"

REVISION:

SHEET NO.:

A2OF

**A4**