

CARE REQUIRED FOR CONCRETE CUTTING AND REMOVAL OPERATIONS NEAR STOREFRONT GLASS.  
 EXCESS RESIDUAL FLOOR COATING TO BE SCRAPED FROM WINDOW HARDWARE AS PART OF WORK, TYP.



TRANSITION AT STOREFRONT GLASS

**BASE DATA NOTES:**

BASE PLAN DATA IS BASED ON THE BEST AVAILABLE AND PROVIDED DATA, BUT IS NOT DERIVED FROM AN ACTUAL AS-BUILT SURVEY BY A REGISTERED PROFESSIONAL SURVEYOR. AS SUCH, THE BASE DATA IS SCHEMATIC IN NATURE AND SITE CONDITIONS MAY VARY. MINOR FIELD ADJUSTMENTS ARE EXPECTED. MAJOR FIELD ADJUSTMENTS SHOULD BE APPROVED BY THE OWNER'S REPRESENTATIVE. FOR THIS PROJECT THE POOL COPING IS POINT OF REFERENCE AND IS SET AT 10' ELEVATION FOR RELATIVE CHANGES IN GRADE.



**DEMOLITION SCHEDULE**

SYMBOL	02 EXISTING CONDITIONS DESCRIPTION	QTY	DETAIL	CONTRACT	OUTCOME
02-01	POOL DECK AREA FLOORING/PAVING, POOL SURROUND AND ADJACENT	5,043 sf		BASE BID	REMOVE
02-02	MENS RESTROOM AREA FLOORING; INCLUDING BUILT UP BASE AND +/- 8 FLOOR DRAIN GRATES - TO BE FILED VERIFIED	1,149 sf		ADD OPT	REMOVE
02-03	WOMENS RESTROOM AREA FLOORING; INCLUDING BUILT UP BASE AND +/- 8 FLOOR DRAIN GRATES - TO BE FILED VERIFIED	1,123 sf		ADD OPT	REMOVE
02-04	OFFICE 1 AREA FLOORING	132 sf		BASE BID	REMOVE
02-05	OFFICE 2 AREA FLOORING	252 sf		BASE BID	REMOVE
02-06	POOL WELL GRATES	12		BASE BID	REMOVE
02-07	STARTING BLOCK ANCHORS; SPECTRUM AQUATICS BY PLAYCORE STARTING BLOCKS; REMOVE AND STORE PER OWNERS DIRECTION; DETACH AND STOW ALL GROUNDING AND OTHER ATTACHMENTS FOR RECONNECTION UPON REINSTALL	12		BASE BID	REMOVE
02-08	CHANNEL DRAINS; REMOVE EXISTING CHANNEL DRAINS; TAKE CARE TO PRESERVE DRAIN PIPE BENEATH FOR CONNECTION OF NEW CHANNEL DRAIN	14		BASE BID	REMOVE
02-09	CLIMBING WALL; REMOVE AND STORE PER OWNERS DIRECTION; DETACH AND STOW ALL GROUNDING AND OTHER ATTACHMENTS FOR RECONNECTION UPON REINSTALL	1		BASE BID	REMOVE
02-10	MENS RESTROOM DRAIN ADD: IN THE EVENT PROPOSED DRAIN ADD-ALTERNATE IS ACCEPTED. SUBSURFACE DEMOLITION TO ACCOMADATE NEW DRAINS WILL BE REQUIRED.	1		ADD OPT	REMOVE
02-11	WOMENS RESTROOM DRAIN ADD: IN THE EVENT PROPOSED DRAIN ADD-ALTERNATE IS ACCEPTED. SUBSURFACE DEMOLITION TO ACCOMADATE NEW DRAINS WILL BE REQUIRED.	1		ADD OPT	REMOVE

**GENERAL NOTES**

ALL AMENITIES, APPARATUSSES, AND ATTACHMENTS NOT LISTED (I.E. SKIMMER COVERS; POOL LADDERS; DEPTH MARKERS) SHALL BE: CATALOGED; LOCATIONS NOTED AND MEASURED; REMOVED; EITHER DISCARD MATERIAL IN APPROPRIATE MANNER FOR REPLACEMENT OR STORE MATERIALS PER OWNERS DIRECTION FOR REINSTALL.



PAVING TRANSITION AT ROLL-UP DOOR

COATING TO BE REMOVED FROM VERTICAL SURFACES. SURFACES TO BE TOUCH-UP REPAINTED AS REQUIRED AS PART OF BASE BID.  
 EXISTING COATING OVER TILE OVER CONCRETE. ALL TO BE REMOVED DURING DEMOLITION PROCESS, TYP. AS PART OF BASE BID.  
 COATING OVERAPPLICATION ON ADJACENT CONCRETE PAVING TO BE REMOVED AS PART OF BASE CONTRACT, TYP.



WELL POINTS - TO REMAIN, REPLACE AT GRADE GRATE

WELL DRAIN GRATES TO BE REMOVED AND REPLACED AS PART OF THE BASE CONTRACT, TYP.



POOL COPING - TO REMAIN, PROTECT DURING WORK

COATING OVERAPPLICATION ON ADJACENT POOL COPING TO BE REMOVED AS PART OF THIS CONTRACT, TYP.  
 POOL COPING, TO REMAIN. CARE REQUIRED FOR CONCRETE CUTTING AND REMOVAL OPERATIONS AT POOL COPING.

Revisions		Revisions / Submissions	
No.	Date		
	01.31.20	PROGRESS REVIEW	

CW \_\_\_\_\_  
 Drawn  
 CW \_\_\_\_\_  
 Checked  
 196002-013  
 Project No.  
 05.14.19  
 Date

Registration  
 STATE OF ALABAMA  
 LESTER CHAD WALKER  
 REGISTERED LANDSCAPE ARCHITECT  
 NUMBER 518

Sheet Title

**DEMOLITION PLAN**

